



SCHEDULE OF COLUMN TIES:-

SL NO.	NO. OF COLUMN	COLUMN SIZE	LONGITUDINAL REINFORCEMENT DETAILS	LATERAL TIES
D	04	230 x 230	8-16 Φ	8 Φ 150

FINISHING SCHEDULE

LEVEL	ROOM DESCRIPTION	TYPE OF FLOORING	TYPE OF SKIRTING/DADO	CEILING FINISHES
GROUND LVL	SECURITY ROOM	VITRIFIED TILES 5.5mm THK. [ITEM 23]		WHITEWASH [ITEM-84]
GROUND LVL	TOILET	CERAMIC TILES 5.5mm THK. [ITEM 24]		WHITEWASH [ITEM-84]

SCHEDULE OF JOINERY

MARK	WIDTH	HEIGHT	QTY.	DESCRIPTION
D	900	2100	1	ALUMINIUM DOOR TO DETAIL
D1	750	2100	1	WOODEN FLUSH DOOR TO DETAIL
W	1200	1200	2	ALUMINIUM WINDOW TO DETAIL
V	900	600	01	ALUMINIUM VENTILATOR TO DETAIL

NOTE:-

- ALL DIMENSIONS ARE IN MILLIMETERS AND ALL LEVELS ARE IN METERS.
- FGL - DENOTES FINISHED GROUND LEVEL & SHALL CORRESPONDS FOR (±)0.00M.
- F.F.L - DENOTES FINISHED FLOOR LEVEL.
- ONLY WRITTEN DIMENSIONS TO BE FOLLOWED AND DRAWING NOT TO BE SCALED.

MATERIAL SPECIFICATION:

- EXTERNAL PLASTER - 20MM THK. CEMENT SAND PLASTER IN 1:3, (ITEM NO.14)
- INTERNAL PLASTER - 15MM THK. CEMENT SAND PLASTER 1:4 (ITEM NO.13)
- ALL EXTERNAL WALLS EXCEPT WHERE MENTIONED SHALL BE FULL BRICK THICK WALL (230mm) IN 1:4 CEMENT SAND MORTAR, (ITEM NO. 12-a)
- ALL INTERNAL WALLS SHALL BE HALF BRICK THK IN 1:4 (C.M) [ITEM NO.12C]
- DAMP PROOF COURSE - 50mm THK. DPC WITH 1:2:4 CONCRETE AS PER SPECIFICATION (ITEM NO. 8)

LEGEND:-

F.G.L. FINISHED GROUND LEVEL
F.F.L. FINISHED FLOOR LEVEL

SECURITY ROOM BUILDING PLAN & SECTION DRAWING

Thecivilstudies || Cad Design services

- 5427PN082-BAR-132-SYD-SRI-S7010-GA-1054 : CONTOUR LAYOUT & BOUNDARY LINE DRAWING
- 5427PN082-BAR-000-SYD-SRI-S2020-GA-0001 : LAYOUT PLAN - OVERALL SWITCHYARD